



CE EMC Test Report

Project No. : 2404G121
Equipment : projector
Brand Name : XGIMI
Test Model : WM03A
Series Model : N/A
Applicant : XGIMI Technology Co., Ltd.
Address : Building No.4, Zone A, No.1129, Shijicheng Road, Chengdu High-tech Zone, Sichuan Pilot Free Trade Zone, China
Manufacturer : XGIMI Technology Co., Ltd.
Address : Building No.4, Zone A, No.1129, Shijicheng Road, Chengdu High-tech Zone, Sichuan Pilot Free Trade Zone, China
Factory : XGIMI Technology Co., Ltd.
Address : Building No.4, Zone A, No.1129, Shijicheng Road, Chengdu High-tech Zone, Sichuan Pilot Free Trade Zone, China
Date of Receipt : May 15, 2024
Date of Test : May 17, 2024 ~ Jun. 12, 2024
Issued Date : Jul. 03, 2024
Report Version : R00
Test Sample : Engineering Sample No.: SSL20240515177
Standard(s) : EN 55032:2015+A11:2020
EN IEC 61000-3-2:2019+A1:2021
EN 61000-3-3:2013+A2:2021
EN 55035:2017+A11:2020

The above equipment has been tested and found compliance with the requirement of the relative standards by BTL Inc.

Prepared by : Ken feng
Ken Feng

Approved by : Kevin Li
Kevin Li

Room 108, Building 2, No.1, Yile Road, Songshan Lake Zone, Dongguan City, Guangdong,
People's Republic of China.

Tel: +86-769-8318-3000 Web: www.newbtl.com Service mail: btl_qa@newbtl.com

Declaration

BTL represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with standards traceable to international standard(s) and/or national standard(s).

BTL's reports apply only to the specific samples tested under conditions. It is manufacture's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **BTL** assumes no responsibility for the data provided by the customer, any statements, inferences or generalizations drawn by the customer or others from the reports issued by **BTL**.

The report must not be used by the client to claim product certification, approval, or endorsement by A2LA or any agency of the U.S. Government.

This report is the confidential property of the client. As a mutual protection to the clients, the public and ourselves, the test report shall not be reproduced, except in full, without our written approval.

BTL's laboratory quality assurance procedures are in compliance with the ISO/IEC 17025: 2017 requirements, and accredited by the conformity assessment authorities listed in this test report.

BTL is not responsible for the sampling stage, so the results only apply to the sample as received.

The information, data and test plan are provided by manufacturer which may affect the validity of results, so it is manufacturer's responsibility to ensure that the apparatus meets the essential requirements of applied standards and in all the possible configurations as representative of its intended use.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

Please note that the measurement uncertainty is provided for informational purpose only and are not use in determining the Pass/Fail results.

Table of Contents	Page
REPORT ISSUED HISTORY	6
1 . SUMMARY OF TEST RESULTS	7
1.1 TEST FACILITY	8
1.2 MEASUREMENT UNCERTAINTY	8
1.3 TEST ENVIRONMENT CONDITIONS	10
2 . GENERAL INFORMATION	11
2.1 GENERAL DESCRIPTION OF EUT	11
2.2 DESCRIPTION OF TEST MODES	12
2.3 EUT OPERATING CONDITIONS	13
2.4 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED	13
2.5 DESCRIPTION OF SUPPORT UNITS	14
3 . EMC EMISSION TEST	15
3.1 RADIATED EMISSIONS UP TO 1 GHZ	15
3.1.1 LIMITS	15
3.1.2 MEASUREMENT INSTRUMENTS LIST	15
3.1.3 TEST PROCEDURE	16
3.1.4 DEVIATION FROM TEST STANDARD	16
3.1.5 TEST SETUP	16
3.1.6 MEASUREMENT DISTANCE	17
3.1.7 TEST RESULTS	18
3.2 RADIATED EMISSIONS ABOVE 1 GHZ	22
3.2.1 LIMITS	22
3.2.2 MEASUREMENT INSTRUMENTS LIST	22
3.2.3 TEST PROCEDURE	23
3.2.4 DEVIATION FROM TEST STANDARD	23
3.2.5 TEST SETUP	23
3.2.6 MEASUREMENT DISTANCE	24
3.2.7 TEST RESULTS	25
3.3 CONDUCTED EMISSION MEASUREMENT AT AC MAINS POWER PORTS	29
3.3.1 LIMITS	29
3.3.2 MEASUREMENT INSTRUMENTS LIST	29
3.3.3 TEST PROCEDURE	29
3.3.4 DEVIATION FROM TEST STANDARD	29
3.3.5 TEST SETUP	30
3.3.6 TEST RESULTS	31
3.4 HARMONIC CURRENT EMISSIONS TEST	35
3.4.1 LIMITS	35
3.4.2 MEASUREMENT INSTRUMENTS LIST	35
3.4.3 TEST PROCEDURE	35

Table of Contents	Page
3.4.4 DEVIATION FROM TEST STANDARD	35
3.4.5 TEST SETUP	35
3.4.6 TEST RESULTS	36
3.5 VOLTAGE FLUCTUATIONS (FLICKER) TEST	39
3.5.1 LIMITS	39
3.5.2 MEASUREMENT INSTRUMENTS LIST	39
3.5.3 TEST PROCEDURE	39
3.5.4 DEVIATION FROM TEST STANDARD	39
3.5.5 TEST SETUP	40
3.5.6 TEST RESULTS	41
4 . EMC IMMUNITY TEST	42
4.1 STANDARD COMPLIANCE/SEVERITY LEVEL/CRITERIA	42
4.2 GENERAL PERFORMANCE CRITERIA	45
4.3 ANNEX G (NORMATIVE) - AUDIO OUTPUT FUNCTION	46
4.3.1 PERFORMANCE CRITERIA	46
4.4 ELECTROSTATIC DISCHARGE IMMUNITY TEST (ESD)	47
4.4.1 TEST SPECIFICATION	47
4.4.2 MEASUREMENT INSTRUMENTS	47
4.4.3 TEST PROCEDURE	47
4.4.4 DEVIATION FROM TEST STANDARD	48
4.4.5 TEST SETUP	48
4.4.6 TEST RESULTS	49
4.5 RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD IMMUNITY TEST (RS)	53
4.5.1 TEST SPECIFICATION	53
4.5.2 MEASUREMENT INSTRUMENTS	53
4.5.3 TEST PROCEDURE	53
4.5.4 DEVIATION FROM TEST STANDARD	54
4.5.5 TEST SETUP	54
4.5.6 TEST RESULTS	56
4.6 ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST (EFT)	59
4.6.1 TEST SPECIFICATION	59
4.6.2 MEASUREMENT INSTRUMENTS	59
4.6.3 TEST PROCEDURE	59
4.6.4 DEVIATION FROM TEST STANDARD	59
4.6.5 TEST SETUP	60
4.6.6 TEST RESULTS	61
4.7 SURGE IMMUNITY TEST (SURGE)	62
4.7.1 TEST SPECIFICATION	62
4.7.2 MEASUREMENT INSTRUMENTS	62
4.7.3 TEST PROCEDURE	62
4.7.4 DEVIATION FROM TEST STANDARD	62
4.7.5 TEST SETUP	63
4.7.6 TEST RESULTS	64

Table of Contents	Page
4.8 IMMUNITY TO CONDUCTED DISTURBANCES, INDUCED BY RADIO-FREQUENCY	
FIELDS TEST (CS)	65
4.8.1 TEST SPECIFICATION	65
4.8.2 MEASUREMENT INSTRUMENTS	65
4.8.3 TEST PROCEDURE	65
4.8.4 DEVIATION FROM TEST STANDARD	66
4.8.5 TEST SETUP	66
4.8.6 TEST RESULTS	68
4.9 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST (PFMF)	71
4.9.1 TEST SPECIFICATION	71
4.9.2 MEASUREMENT INSTRUMENTS	71
4.9.3 TEST PROCEDURE	71
4.9.4 DEVIATION FROM TEST STANDARD	71
4.9.5 TEST SETUP	72
4.9.6 TEST RESULTS	73
4.10 VOLTAGE DIPS, SHORT INTERRUPTIONS AND VOLTAGE VARIATIONS IMMUNITY	
TEST (DIPS)	74
4.10.1 TEST SPECIFICATION	74
4.10.2 MEASUREMENT INSTRUMENTS	74
4.10.3 TEST PROCEDURE	74
4.10.4 DEVIATION FROM TEST STANDARD	74
4.10.5 TEST SETUP	75
4.10.6 TEST RESULTS	76
5 . EUT TEST PHOTO	77

REPORT ISSUED HISTORY

Report No.	Version	Description	Issued Date	Note
BTL-EMC-1-2404G121	R00	Original Report.	Jul. 03, 2024	Valid

1. SUMMARY OF TEST RESULTS

Test procedures according to the technical standards:

Emission			
Standard(s)	Test Item		Result
EN 55032:2015+A11:2020	Radiated emissions up to 1 GHz		PASS
	Radiated emissions above 1 GHz		PASS
	Radiated emissions from FM receivers		N/A
	Conducted emissions AC mains power port		PASS
	Asymmetric mode conducted emissions	AAN	N/A
		Current Probe	N/A
		CP+CVP	N/A
	Conducted differential voltage emissions		N/A

Standard(s)	Test Item	Result
EN IEC 61000-3-2:2019+A1:2021	Harmonic current	PASS
EN 61000-3-3:2013+A2:2021	Voltage fluctuations (Flicker)	PASS

Immunity			
Standard(s)	Ref Standard(s)	Test Item	Result
EN 55035:2017+A11:2020	IEC 61000-4-2:2008	ESD	PASS
	IEC 61000-4-3:2020	RS	PASS
	IEC 61000-4-4:2012	EFT	PASS
	IEC 61000-4-5:2014+AMD1:2017	Surge	PASS
	IEC 61000-4-6:2013 IEC 61000-4-6:2023	CS	PASS
	IEC 61000-4-8:2009	PFMF	PASS
	IEC 61000-4-11:2020	Dips	PASS

Standard(s)	Section	Test Item	Result
EN 55035:2017+A11:2020	4.2.7	BIN-R	N/A
	4.2.7	BIN-I	N/A

NOTE:

(1) "N/A" denotes test is not applicable to this device.

1.1 TEST FACILITY

The test facilities used to collect the test data in this report is at the location of Room 108, Building 2, No.1, Yile Road, Songshan Lake Zone, Dongguan City, Guangdong, People's Republic of China.

1.2 MEASUREMENT UNCERTAINTY

Where relevant, the following measurement uncertainty levels have been estimated for tests performed on the EUT as specified in CISPR 16-4-2, The BTL measurement uncertainty is less than the CISPR 16-4-2 U_{CISPR} requirement.

The reported uncertainty of measurement $y \pm U$, where expanded uncertainty U is based on a standard uncertainty multiplied by a coverage factor of $k=2$, providing a level of confidence of approximately **95%**.

A. Radiated emissions up to 1 GHz measurement:

Test Site	Method	Measurement Frequency Range	Ant. H / V	U , (dB)
SSL-CB01 (3m)	CISPR	30MHz ~ 200MHz	V	4.70
		30MHz ~ 200MHz	H	3.56
		200MHz ~ 1,000MHz	V	4.92
		200MHz ~ 1,000MHz	H	4.54

B. Radiated emissions above 1 GHz measurement:

Test Site	Method	Measurement Frequency Range	U , (dB)
SSL-CB01 (3m)	CISPR	1GHz ~ 6GHz	4.56

C. Conducted emissions AC mains power port measurement:

Test Site	Method	Measurement Frequency Range	U , (dB)
SSL-C01	CISPR	150kHz ~ 30MHz	2.68

D. Harmonic current / Voltage fluctuations (Flicker) measurement:

Test Site	Method	Item	U (%)
SSL-C01	EN IEC 61000-3-2 EN 61000-3-3	Voltage	0.817
		Current	0.817

E. Immunity Measurement:

Test Site	Method	Item	U
SSL-SR02	IEC 61000-4-2	Rise time tr	6.7%
		Peak current Ip	6.5%
		Current at 30 ns	6.4%
		Current at 60 ns	6.4%
SSL-CB03	IEC 61000-4-3 (80MHz~6GHz)	Electromagnetic field immunity test	2.26dB
		On-ear acoustic & Acoustic measurements on loudspeakers	2.28dB
SSL-SR01	IEC 61000-4-4	Peak voltage (VP)	3.7%
		Rise time (tr)	4.4%
		Pulse width(tw)	4.2%
		Pulse Freq.(kHz)	0.7%
		Burst Duration(ms)	1.4%
		Burst Period(ms)	1.4%
SSL-SR01	IEC 61000-4-5	Open-Circuit Output Voltage (1.2/50us)	4.0%
		Open circuit front time (1.2/50us)	6.1%
		Open circuit time of half value (1.2/50us)	4.7%
SSL-CB02	IEC 61000-4-6 (150kHz-80MHz)	CDN	1.28dB
		On-ear acoustic & Acoustic measurements on loudspeakers	1.28dB
SSL-SR01	IEC 61000-4-8	Magnetic Field Strength	1.91%
SSL-SR01	IEC 61000-4-11	DIP Amplitude	3.6%
		DIP Time Event	4.0%

Note: Unless specifically mentioned, the uncertainty of measurement has not been taken into account to declare the compliance or non-compliance to the specification.

1.3 TEST ENVIRONMENT CONDITIONS

Test Item	Temperature	Humidity	Tested By	Test Date
Radiated emissions up to 1 GHz	24°C	43%	Nolan Zhang	May 28 2024
Radiated emissions above 1 GHz	24°C	43%	Nolan Zhang	May 28 2024
Conducted emissions AC mains power port	24°C	45%	Harry Tan	May 27, 2024
Harmonic current	24°C	45%	Harry Tan	May 24 2024
Voltage fluctuations (Flicker)	24°C	45%	Harry Tan	May 24 2024

Test Item	Temperature	Humidity	Pressure	Tested By	Test Date
ESD	25°C	50%	1007hPa	Geoffrey	May 21, 2024
RS	23°C	56%	/	Niko Zhao	May 29, 2024
EFT	20°C	63%	/	Leonard Li	May 30, 2024
Surge	20 C	63%		Leonard Li	May 30, 2024
CS	22°C	66%	/	Edison Yi	May 22, 2024
PFMF	20°C	63%	/	Leonard Li	May 30, 2024
Dips	20°C	63%	/	Leonard Li	May 30, 2024

2. GENERAL INFORMATION

2.1 GENERAL DESCRIPTION OF EUT

Equipment	projector
Brand Name	XGIMI
Test Model	WM03A
Series Model	N/A
Model Difference(s)	N/A
Identification No. of EUT(S/N)	N/A
Dimensions and mass	129*53*30mm
Component unit of EUT	☐ Single unit ☒ Multiple unit
Sample Status	☒ Engineering sample ☐ Final shipment prototype
Power Source	DC voltage supplied from AC adapter. Model:HKA09019047-6P
Power Rating	INPUT:100-240V~ 1.5A 50/60Hz OUTPUT:19.0V===4.74A
Connecting I/O Port(s)	1*DC IN port 1*Earphone port 1*HDMI port 1*USB2.0 port
Classification of EUT	Class B
Highest Internal Frequency(Fx)	Exceeds 108 MHz

Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the user's manual.

2.2 DESCRIPTION OF TEST MODES

To investigate the maximum EMI emission characteristics generates from EUT, the test system was pre-scanning tested base on the consideration of following EUT operation mode or test configuration mode which possible have effect on EMI emission level. Each of these EUT operation mode(s) or test configuration mode(s) mentioned above was evaluated respectively.

Pretest Mode	Description
Mode 1	FULL SYSTEM HDMI:1920x1080(1080p)
Mode 2	FULL SYSTEM(USB PLAY)
Mode 3	FULL SYSTEM(WIFI PLAY)+(BT PLAY)

Radiated emissions up to 1 GHz Test	
Final Test Mode	Description
Mode 1	FULL SYSTEM HDMI:1920x1080(1080p)

Radiated emissions Above 1 GHz Test	
Final Test Mode	Description
Mode 2	FULL SYSTEM(USB PLAY)

Conducted emissions AC mains power port Test	
Final Test Mode	Description
Mode 2	FULL SYSTEM(USB PLAY)

Harmonic current & Voltage fluctuations (Flicker) Test	
Final Test Mode	Description
Mode 1	FULL SYSTEM HDMI:1920x1080(1080p)

Immunity Test	
Final Test Mode	Description
Mode 1	FULL SYSTEM HDMI:1920x1080(1080p)
Mode 2	FULL SYSTEM(USB PLAY)
Mode 3	FULL SYSTEM(WIFI PLAY)+(BT PLAY)

Note:


1. For EMI: Evaluated the mode 1-3. The worst case is recorded in this report.
2. The product supports BT&2.4G&5G WIFI function.
The frequency exemptions are 2400-2483.5MHz, 5150-5250MHz, 5250-5350MHz, 5470-5725MHz, 5725-5850MHz.
3. Radiated emission above 1GHz tested with 2.4G&5G filter.
4. RS: The Front, Rear, Left and Right were evaluated. The worst placement direction is Left and recorded in this report.
5. The audio output function of CS/RS is recorded the worst mode.

2.3 EUT OPERATING CONDITIONS

The EUT exercise program used during radiated and/or conducted emission measurement was designed to exercise the various system components in a manner similar to a typical use. The standard test signals and output signal as following:

1. USB Flash is plugged into EUT.
2. EUT connected to Earphone via Earphone Cable.
3. EUT connected to Adapter via DC Cable.
4. EUT connected to PC via HDMI Cable.
5. Mouse and Keyboard connected to PC via USB Cable.
6. EUT connected to Bluetooth Earphone via BT.
7. EUT connected to Router via WIFI.

2.4 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED



2.5 DESCRIPTION OF SUPPORT UNITS

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

Item	Equipment	Mfr/Brand	Model/Type No.	Series No.
A	USB Flash	N/A	N/A	N/A
B	Earphone	Apple	N/A	N/A
C	PC	DELL	Optiplex 7080	N/A
D	Mouse	DELL	MS111-P	CN011D3V71581279OLOT
E	Keyboard	DELL	KB212-B	CN0HTXH97158125004DXA01
F	Router	ASUS	TE-AC66U	E8ICGG00013
G	Bluetooth Earphone	MICROKIA	M9	N/A

Item	Cable Type	Shielded Type	Ferrite Core	Length
1	AC Cable	NO	NO	1.8m
2	DC Cable	NO	YES	1.0m
3	Earphone Cable	NO	NO	1.2m
4	HDMI Cable	YES	NO	1.8m
5	USB Cable	YES	NO	1.5m
6	USB Cable	YES	NO	1.5m

3. EMC EMISSION TEST

3.1 RADIATED EMISSIONS UP TO 1 GHZ

3.1.1 LIMITS

Class B equipment up to 1 GHz

Frequency Range MHz	Measurement			Class B limits dB(μV/m)
	Facility	Distance m	Detector type/ bandwidth	
30 - 230	SAC	3	Quasi peak / 120 kHz	40
230 - 1000				47

Notes:

- (1) The limit for radiated test was performed according to as following: EN 55032
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:
 Measurement Value = Reading Level + Correct Factor
 Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)
 Margin Level = Measurement Value - Limit Value

3.1.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Trilog-Broadband Antenna	Schwarzbeck	VULB9168	01587	Apr. 25, 2025
2	Attenuator	EMCI	VFA_Z04002-N-06	N/A	Apr. 25, 2025
3	MXE EMI Receiver	Keysight	N9038A	MY59050118	Sep. 26, 2024
4	Preamplifier	EMC INSTRUMENT	EMC001330	980825	Jan. 19, 2025
5	Cable	EMC INSTRUMENT	EMCCFD400-NM-NM-2500	N/A	Jun. 08, 2024
6	Cable	EMC INSTRUMENT	EMCCFD400-NM-NM-7000	N/A	Jun. 08, 2024
7	Cable	EMC INSTRUMENT	EMCCFD400-NM-NM-3000	N/A	Jun. 08, 2024
8	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-01	N/A	N/A

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.1.3 TEST PROCEDURE

- The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.
- The height of the equipment or of the substitution antenna shall be 0.8 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform.
- For the actual test configuration, please refer to the related Item - EUT Test Photos.

3.1.4 DEVIATION FROM TEST STANDARD

No deviation

3.1.5 TEST SETUP



3.1.6 MEASUREMENT DISTANCE




Figure C.1 – Measurement distance





Figure C.2 – Boundary of EUT, Local AE and associated cabling


3.1.7 TEST RESULTS

Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Mode 1		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		40.6700	44.70	-12.25	32.45	40.00	-7.55	QP	
2		127.0000	43.73	-13.41	30.32	40.00	-9.68	QP	
3		170.6500	45.57	-12.22	33.35	40.00	-6.65	QP	
4	I	196.8400	48.85	-14.70	34.15	40.00	-5.85	QP	
5	*	222.0600	50.27	-14.71	35.56	40.00	-4.44	QP	
6		599.8750	41.92	-3.75	38.17	47.00	-8.83	QP	

Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Mode 1		




No.	Mk.	Freq.	Reading Level	Correct Factor	Measurement	Limit	Margin		
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comment
1		48.9150	35.56	-11.91	23.65	40.00	-16.35	QP	
2		124.5750	39.07	-13.61	25.46	40.00	-14.54	QP	
3		167.2550	43.62	-11.98	31.64	40.00	-8.36	QP	
4		197.3250	47.22	-14.73	32.49	40.00	-7.51	QP	
5	*	224.4850	49.08	-14.49	34.59	40.00	-5.41	QP	
6		390.8400	49.26	-9.02	40.24	47.00	-6.76	QP	

Test Voltage	AC 110V/60Hz	Polarization	Vertical
Test Mode	Mode 1		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1	!	60.5550	47.60	-12.44	35.16	40.00	-4.84	QP	
2	*	128.9400	49.28	-13.23	36.05	40.00	-3.95	QP	
3		167.7400	45.89	-12.01	33.88	40.00	-6.12	QP	
4		195.3850	46.42	-14.61	31.81	40.00	-8.19	QP	
5	!	226.9100	49.34	-14.30	35.04	40.00	-4.96	QP	
6		607.1500	43.54	-3.70	39.84	47.00	-7.16	QP	

Test Voltage	AC 110V/60Hz	Polarization	Horizontal
Test Mode	Mode 1		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		61.0400	38.69	-12.50	26.19	40.00	-13.81	QP	
2		163.8600	44.80	-11.77	33.03	40.00	-6.97	QP	
3		252.1300	46.49	-12.85	33.64	47.00	-13.36	QP	
4	*	371.4400	50.64	-9.50	41.14	47.00	-5.86	QP	
5		455.3450	44.16	-7.21	36.95	47.00	-10.05	QP	
6		605.6950	40.22	-3.71	36.51	47.00	-10.49	QP	

3.2 RADIATED EMISSIONS ABOVE 1 GHZ

3.2.1 LIMITS

Class B equipment above 1 GHz

Frequency Range MHz	Measurement			Class B limits dB(μV/m)
	Facility	Distance m	Detector type/bandwidth	
1000 - 3000	FSOATS	3	Average / 1 MHz	50
3000 - 6000				54
1000 - 3000			Peak / 1 MHz	70
3000 - 6000				74

Notes:

- (1) The limit for radiated test was performed according to as following: EN 55032
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:
 Measurement Value = Reading Level + Correct Factor
 Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)
 Margin Level = Measurement Value - Limit Value

Required highest frequency for radiated measurement

Highest internal frequency (F _x)	Highest measured frequency
F _x ≤ 108 MHz	1 GHz
108 < F _x ≤ 500 MHz	2 GHz
500 < F _x ≤ 1000 MHz	5 GHz
F _x > 1 GHz	5 x F _x up to a maximum of 6 GHz

3.2.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	MXE EMI Receiver	Keysight	N9038A	MY59050118	Sep. 26, 2024
2	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-01	N/A	N/A
3	Preamplifier	EMC INSTRUMENT	EMC118A45SE	980739	Jan. 19, 2025
4	Cable	EMC INSTRUMENT	EMC104-SM-SM-10000	N/A	Jun. 08, 2024
5	Cable	EMC INSTRUMENT	EMC104-SM-SM-3000	N/A	Jun. 08, 2024
6	Cable	EMC INSTRUMENT	EMC104-SM-SM-800	N/A	Jun. 08, 2024
7	Double Ridged Broadband Horn Antenna	RF SPIN	DRH18-E	210106A18E	Jul. 04, 2024

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.2.3 TEST PROCEDURE

- The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 3 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.
- The height of the equipment or of the substitution antenna shall be 0.8 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then AVG detector mode re-measured.
- All readings are Peak Mode value unless otherwise stated AVG in column of Note. If the Peak Mode Measured value compliance with the Peak Limits and lower than AVG Limits, the EUT shall be deemed to meet both Peak & AVG Limits and then only Peak Mode was measured, but AVG Mode didn't perform.
- For the actual test configuration, please refer to the related Item - EUT Test Photos.

3.2.4 DEVIATION FROM TEST STANDARD

No deviation

3.2.5 TEST SETUP



3.2.6 MEASUREMENT DISTANCE




Figure C.1 – Measurement distance





Figure C.2 – Boundary of EUT, Local AE and associated cabling


3.2.7 TEST RESULTS

Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Mode 2		
Note	5G WIFI (5150-5350MHz) is intentional transmissions, which is not applicable to the radiation emission requirements in this standard.		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		1600.000	56.30	-6.20	50.10	70.00	-19.90	peak	
2		1600.000	46.33	-6.20	40.13	50.00	-9.87	AVG	
3		1820.000	56.78	-5.61	51.17	70.00	-18.83	peak	
4		1820.000	44.28	-5.61	38.67	50.00	-11.33	AVG	
5		2227.500	56.19	-4.69	51.50	70.00	-18.50	peak	
6	*	2227.500	45.42	-4.69	40.73	50.00	-9.27	AVG	
7		3035.000	50.19	-2.76	47.43	74.00	-26.57	peak	
8		3035.000	30.92	-2.76	28.16	54.00	-25.84	AVG	
9		4245.000	43.86	0.50	44.36	74.00	-29.64	peak	
10		4245.000	33.16	0.50	33.66	54.00	-20.34	AVG	
11		5150.000	38.55	2.80	41.35	74.00	-32.65	peak	
12		5350.000	37.33	2.79	40.12	54.00	-13.88	AVG	

Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Mode 2		
Note	5G WIFI (5150-5350MHz) is intentional transmissions, which is not applicable to the radiation emission requirements in this standard.		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		1412.500	49.55	-6.66	42.89	70.00	-27.11	peak	
2		1412.500	39.14	-6.66	32.48	50.00	-17.52	AVG	
3		1595.000	52.29	-6.21	46.08	70.00	-23.92	peak	
4		1595.000	43.18	-6.21	36.97	50.00	-13.03	AVG	
5		1827.500	51.37	-5.60	45.77	70.00	-24.23	peak	
6		1827.500	41.18	-5.60	35.58	50.00	-14.42	AVG	
7		2217.500	48.99	-4.72	44.27	70.00	-25.73	peak	
8		2217.500	38.62	-4.72	33.90	50.00	-16.10	AVG	
9		2627.500	55.97	-3.84	52.13	70.00	-17.87	peak	
10	*	2627.500	45.42	-3.84	41.58	50.00	-8.42	AVG	
11		5150.000	36.28	2.80	39.08	74.00	-34.92	peak	
12		5350.000	36.76	2.79	39.55	54.00	-14.45	AVG	

Test Voltage	AC 110V/60Hz	Polarization	Vertical
Test Mode	Mode 2		
Note	5G WIFI (5150-5350MHz) is intentional transmissions, which is not applicable to the radiation emission requirements in this standard.		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		1597.500	56.67	-6.20	50.47	70.00	-19.53	peak	
2		1597.500	36.88	-6.20	30.68	50.00	-19.32	AVG	
3		1817.500	54.34	-5.62	48.72	70.00	-21.28	peak	
4	*	1817.500	46.17	-5.62	40.55	50.00	-9.45	AVG	
5		2222.500	54.54	-4.71	49.83	70.00	-20.17	peak	
6		2222.500	44.83	-4.71	40.12	50.00	-9.88	AVG	
7		2630.000	50.32	-3.82	46.50	70.00	-23.50	peak	
8		2630.000	40.05	-3.82	36.23	50.00	-13.77	AVG	
9		3032.500	51.14	-2.75	48.39	74.00	-25.61	peak	
10		3032.500	41.42	-2.75	38.67	54.00	-15.33	AVG	
11		5150.000	36.66	2.80	39.46	74.00	-34.54	peak	
12		5350.000	36.91	2.79	39.70	54.00	-14.30	AVG	

Test Voltage	AC 110V/60Hz	Polarization	Horizontal
Test Mode	Mode 2		
Note	5G WIFI (5150-5350MHz) is intentional transmissions, which is not applicable to the radiation emission requirements in this standard.		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		1415.000	50.97	-6.65	44.32	70.00	-25.68	peak	
2		1415.000	30.28	-6.65	23.63	50.00	-26.37	AVG	
3		1592.500	51.46	-6.21	45.25	70.00	-24.75	peak	
4		1592.500	41.08	-6.21	34.87	50.00	-15.13	AVG	
5		1817.500	52.76	-5.62	47.14	70.00	-22.86	peak	
6		1817.500	42.57	-5.62	36.95	50.00	-13.05	AVG	
7		2630.000	54.67	-3.82	50.85	70.00	-19.15	peak	
8	*	2630.000	44.66	-3.82	40.84	50.00	-9.16	AVG	
9		3027.500	47.41	-2.77	44.64	74.00	-29.36	peak	
10		3027.500	37.15	-2.77	34.38	54.00	-19.62	AVG	
11		5150.000	36.60	2.80	39.40	74.00	-34.60	peak	
12		5350.000	37.08	2.79	39.87	54.00	-14.13	AVG	

3.3 CONDUCTED EMISSION MEASUREMENT AT AC MAINS POWER PORTS

3.3.1 LIMITS

Requirements for conducted emissions from AC mains power ports of Class B equipment

Frequency Range MHz	Coupling Device	Detector Type / bandwidth	Class B Limits (dB(μV))
0.15 - 0.5	AMN	Quasi Peak / 9 kHz	66-56
0.5 - 5			56
5 - 30			60
0.15 - 0.5	AMN	Average / 9 kHz	56-46
0.5 - 5			46
5 - 30			50

NOTE:

(1) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor(if use)

Margin Level = Measurement Value – Limit Value

3.3.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	TWO-LINE V-NETWORK	R&S	ENV216	102771	Sep. 25, 2024
2	EMI Test Receiver	R&S	ESCI	100895	Jan. 19, 2025
3	Cable	N/A	RG400	N/A	Mar. 05, 2025
4	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-01	N/A	N/A
5	Artificial-Mains Network	Schwarzbeck	NSLK 8127	01085	Jul. 12, 2024

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.3.3 TEST PROCEDURE

- The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipment powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- LISN at least 80 cm from nearest part of EUT chassis.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

3.3.4 DEVIATION FROM TEST STANDARD


No deviation

3.3.5 TEST SETUP




3.3.6 TEST RESULTS

Test Voltage	AC 230V/50Hz	Phase	Line
Test Mode	Mode 2		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.2355	44.04	9.68	53.72	62.25	-8.53	QP	
2		0.2355	33.10	9.68	42.78	52.25	-9.47	AVG	
3	*	0.6090	38.95	9.72	48.67	56.00	-7.33	QP	
4		0.6090	27.20	9.72	36.92	46.00	-9.08	AVG	
5		0.8250	36.94	9.72	46.66	56.00	-9.34	QP	
6		0.8250	25.60	9.72	35.32	46.00	-10.68	AVG	
7		1.1580	38.59	9.72	48.31	56.00	-7.69	QP	
8		1.1580	27.30	9.72	37.02	46.00	-8.98	AVG	
9		8.5155	30.72	10.07	40.79	60.00	-19.21	QP	
10		8.5155	19.80	10.07	29.87	50.00	-20.13	AVG	
11		14.3475	32.39	10.40	42.79	60.00	-17.21	QP	
12		14.3475	21.50	10.40	31.90	50.00	-18.10	AVG	

Test Voltage	AC 230V/50Hz	Phase	Neutral
Test Mode	Mode 2		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1545	40.34	9.68	50.02	65.75	-15.73	QP	
2		0.1545	29.10	9.68	38.78	55.75	-16.97	AVG	
3		0.2400	38.98	9.69	48.67	62.10	-13.43	QP	
4		0.2400	27.20	9.69	36.89	52.10	-15.21	AVG	
5	*	0.5730	40.32	9.73	50.05	56.00	-5.95	QP	
6		0.5730	29.30	9.73	39.03	46.00	-6.97	AVG	
7		1.1760	37.93	9.76	47.69	56.00	-8.31	QP	
8		1.1760	26.50	9.76	36.26	46.00	-9.74	AVG	
9		7.6560	30.02	10.05	40.07	60.00	-19.93	QP	
10		7.6560	19.70	10.05	29.75	50.00	-20.25	AVG	
11		14.1450	31.50	10.52	42.02	60.00	-17.98	QP	
12		14.1450	20.60	10.52	31.12	50.00	-18.88	AVG	

Test Voltage	AC 110V/60Hz	Phase	Line
Test Mode	Mode 2		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1	*	0.1500	44.09	9.66	53.75	66.00	-12.25	QP	
2		0.1500	33.10	9.66	42.76	56.00	-13.24	AVG	
3		0.2265	39.42	9.68	49.10	62.58	-13.48	QP	
4		0.2265	28.70	9.68	38.38	52.58	-14.20	AVG	
5		0.4425	34.71	9.70	44.41	57.01	-12.60	QP	
6		0.4425	23.20	9.70	32.90	47.01	-14.11	AVG	
7		0.9555	31.75	9.73	41.48	56.00	-14.52	QP	
8		0.9555	20.30	9.73	30.03	46.00	-15.97	AVG	
9		6.6930	31.95	9.99	41.94	60.00	-18.06	QP	
10		6.6930	20.50	9.99	30.49	50.00	-19.51	AVG	
11		14.3925	31.42	10.41	41.83	60.00	-18.17	QP	
12		14.3925	20.60	10.41	31.01	50.00	-18.99	AVG	

Test Voltage	AC 110V/60Hz	Phase	Neutral
Test Mode	Mode 2		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1950	40.00	9.69	49.69	63.82	-14.13	QP	
2		0.1950	29.10	9.69	38.79	53.82	-15.03	AVG	
3		0.2580	35.87	9.69	45.56	61.50	-15.94	QP	
4		0.2580	24.80	9.69	34.49	51.50	-17.01	AVG	
5	*	0.4335	34.87	9.72	44.59	57.19	-12.60	QP	
6		0.4335	23.20	9.72	32.92	47.19	-14.27	AVG	
7		0.9555	31.78	9.76	41.54	56.00	-14.46	QP	
8		0.9555	20.30	9.76	30.06	46.00	-15.94	AVG	
9		6.7065	31.78	10.01	41.79	60.00	-18.21	QP	
10		6.7065	20.50	10.01	30.51	50.00	-19.49	AVG	
11		14.2395	31.37	10.53	41.90	60.00	-18.10	QP	
12		14.2395	20.60	10.53	31.13	50.00	-18.87	AVG	

3.4 HARMONIC CURRENT EMISSIONS TEST

3.4.1 LIMITS

The power consumption is less than 75W, there is no limit applied.

3.4.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Harmonic current/voltage wave analyzer	EMC Partner	HAR1000-1P230V	103488-0270	Sep. 21, 2024
2	Measurement Software	EMC-PARTNER	Harmonics-1000	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


3.4.3 TEST PROCEDURE

- The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the maximum harmonic components under normal operating conditions.
- The classification of EUT is according to of EN IEC 61000-3-2. The EUT is classified as Class A.
- The correspondent test program of test instrument to measure the current harmonics emanated from EUT is chosen. The measure time shall be not less than the time necessary for the EUT to be exercised.

3.4.4 DEVIATION FROM TEST STANDARD


No deviation

3.4.5 TEST SETUP



3.4.6 TEST RESULTS

Harmonics – Class-A	
Test Voltage	AC 230V/50Hz
Test Mode	Mode 1



Harmonic Emission - IEC 61000-3-2 , EN 61000-3-2 , (EN60555-2)

2024/5/24 23:11:45

Urms = 220.1 V P = 60.13 W THC = 0.082 A
Irms = 0.293 A pf = 0.933

Range: 50 A
V-nom: 220 V
TestTime: 3 min (100%)

Test completed, Result: PASSED

Current Test Result Summary (Run time)

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

THDi = 30.5 % THDu = 0.10 % Class A

Test - Time : 3min (100 %)

Test completed, Result: PASSED

Order	Freq. [Hz]	Iavg [A]	Irms [A]	Imax [A]	Limit [A]	Status	Vrms [V]	Vmax [V]	Limit [V]
1	50	0.2801	0.2808	0.2899			220.14	220.14	0.0000
2	100	0.0000	0.0031	0.0061	1.0800		0.1718	0.1963	0.4418
3	150	0.0798	0.0793	0.0824	2.3000		0.0491	0.0736	1.9879
4	200	0.0000	0.0000	0.0061	0.4300		0.0245	0.0491	0.4418
5	250	0.0126	0.0122	0.0427	1.1400		0.0245	0.0491	0.8835
6	300	0.0000	0.0000	0.0061	0.3000		0.0245	0.0245	0.4418
7	350	0.0089	0.0092	0.0427	0.7700		0.0245	0.0245	0.6626
8	400	0.0000	0.0000	0.0061	0.2300		0.0245	0.0245	0.4418
9	450	0.0065	0.0061	0.0397	0.4000		0.0245	0.0245	0.4418
10	500	0.0000	0.0000	0.0031	0.1840		0.0000	0.0245	0.4418
11	550	0.0005	0.0031	0.0397	0.3300		0.0245	0.0491	0.2209
12	600	0.0000	0.0000	0.0031	0.1533		0.0000	0.0245	0.2209
13	650	0.0004	0.0031	0.0336	0.2100		0.0000	0.0245	0.2209
14	700	0.0000	0.0000	0.0031	0.1314		0.0000	0.0000	0.2209
15	750	0.0013	0.0031	0.0336	0.1500		0.0000	0.0245	0.2209
16	800	0.0000	0.0000	0.0031	0.1150		0.0000	0.0000	0.2209
17	850	0.0009	0.0031	0.0305	0.1324		0.0000	0.0245	0.2209
18	900	0.0000	0.0000	0.0031	0.1022		0.0000	0.0000	0.2209
19	950	0.0003	0.0031	0.0275	0.1184		0.0000	0.0245	0.2209
20	1000	0.0000	0.0000	0.0031	0.0920		0.0000	0.0000	0.2209
21	1050	0.0003	0.0031	0.0244	0.1071		0.0000	0.0245	0.2209
22	1100	0.0000	0.0000	0.0031	0.0836		0.0000	0.0000	0.2209
23	1150	0.0003	0.0031	0.0214	0.0978		0.0000	0.0245	0.2209
24	1200	0.0000	0.0000	0.0031	0.0767		0.0000	0.0000	0.2209
25	1250	0.0002	0.0031	0.0183	0.0900		0.0000	0.0245	0.2209
26	1300	0.0000	0.0000	0.0000	0.0708		0.0000	0.0000	0.2209
27	1350	0.0002	0.0031	0.0153	0.0833		0.0000	0.0245	0.2209
28	1400	0.0000	0.0000	0.0000	0.0657		0.0000	0.0000	0.2209
29	1450	0.0001	0.0000	0.0122	0.0776		0.0000	0.0245	0.2209
30	1500	0.0000	0.0000	0.0000	0.0613		0.0000	0.0000	0.2209
31	1550	0.0001	0.0000	0.0092	0.0726		0.0000	0.0245	0.2209
32	1600	0.0000	0.0000	0.0000	0.0575		0.0000	0.0000	0.2209
33	1650	0.0001	0.0031	0.0092	0.0682		0.0000	0.0245	0.2209
34	1700	0.0000	0.0000	0.0000	0.0541		0.0000	0.0000	0.2209
35	1750	0.0000	0.0031	0.0061	0.0643		0.0000	0.0000	0.2209
36	1800	0.0000	0.0000	0.0000	0.0511		0.0000	0.0245	0.2209
37	1850	0.0000	0.0000	0.0031	0.0608		0.0000	0.0245	0.2209
38	1900	0.0000	0.0000	0.0000	0.0484		0.0000	0.0245	0.2209
39	1950	0.0000	0.0031	0.0031	0.0577		0.0000	0.0245	0.2209
40	2000	0.0000	0.0000	0.0000	0.0460		0.0000	0.0245	0.2209

Voltage Source Verification Data (Run time)	
Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

Order	Limits in Ampere			
	90%	100%	150%	200%
2	0.9723	1.0803	1.6205	2.1606
3	2.0709	2.3010	3.4515	4.6021
4	0.3873	0.4303	0.6454	0.8606
5	1.0272	1.1414	1.7120	2.2827
6	0.2692	0.2991	0.4486	0.5981
7	0.6921	0.7690	1.1536	1.5381
8	0.2060	0.2289	0.3433	0.4578
9	0.3598	0.3998	0.5997	0.7996
10	0.1648	0.1831	0.2747	0.3662
11	0.2966	0.3296	0.4944	0.6592
12	0.1373	0.1526	0.2289	0.3052
13	0.1895	0.2106	0.3159	0.4211
14	0.1181	0.1312	0.1968	0.2625
15	0.1346	0.1495	0.2243	0.2991
16	0.1044	0.1160	0.1740	0.2319
17	0.1181	0.1312	0.1968	0.2625
18	0.0906	0.1007	0.1511	0.2014
19	0.1071	0.1190	0.1785	0.2380
20	0.0824	0.0916	0.1373	0.1831
21 *	0.0961	0.1068	0.1602	0.2136
22	0.0742	0.0824	0.1236	0.1648
23 *	0.0879	0.0977	0.1465	0.1953
24	0.0687	0.0763	0.1144	0.1526
25 *	0.0797	0.0885	0.1328	0.1770
26	0.0632	0.0702	0.1053	0.1404
27 *	0.0742	0.0824	0.1236	0.1648
28	0.0604	0.0671	0.1007	0.1343
29 *	0.0687	0.0763	0.1144	0.1526
30	0.0549	0.0610	0.0916	0.1221
31 *	0.0659	0.0732	0.1099	0.1465
32	0.0522	0.0580	0.0870	0.1160
33 *	0.0604	0.0671	0.1007	0.1343
34	0.0494	0.0549	0.0824	0.1099
35 *	0.0577	0.0641	0.0961	0.1282
36	0.0467	0.0519	0.0778	0.1038
37 *	0.0549	0.0610	0.0916	0.1221
38	0.0439	0.0488	0.0732	0.0977
39 *	0.0522	0.0580	0.0870	0.1160
40	0.0412	0.0458	0.0687	0.0916

3.5 VOLTAGE FLUCTUATIONS (FLICKER) TEST

3.5.1 LIMITS

Tests	Limits	Descriptions
	EN 61000-3-3	
Pst	≤ 1.0 , $T_p = 10$ min.	Short Term Flicker Indicator
Plt	≤ 0.65 , $T_p = 2$ hr.	Long Term Flicker Indicator
dc	$\leq 3.3\%$	Relative Steady-State V-Change
dmax	$\leq 4\%$	Maximum relative V-change
d (t)	≤ 500 ms	Relative V-change characteristic

3.5.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Harmonic current/voltage wave analyzer	EMC Partner	HAR1000-1P230V	103488-0270	Sep. 21, 2024
2	Measurement Software	EMC-PARTNER	Harmonics-1000	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


3.5.3 TEST PROCEDURE

- Tests was performed according to the Test Conditions/Assessment of Voltage Fluctuations specified in EN 61000-3-3 depend on which standard adopted for compliance measurement.
- All types of harmonic current and/or voltage fluctuation in this report are assessed by direct measurement using flicker-meter.

3.5.4 DEVIATION FROM TEST STANDARD

No deviation


3.5.5 TEST SETUP



3.5.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

Flicker Emission IEC 61000-4-15 for 230V/50Hz



Actual Flicker (Fli):	0.00
Short-term Flicker (Pst):	0.07
Limit (Pst):	1.00
Long-term Flicker (Plt):	0.07
Limit (Plt):	0.65
Maximum Relative Volt. Change (dmax):	0.00%
Limit (dmax):	4.00%
Relative Steady-state Voltage Change (dc):	0.00%
Limit (dc):	3.30%
Tmax 3.00% (dt):	0.00ms
Limit (dt>Lim):	500ms

Flicker Emission - IEC 61000-3-3, EN 61000-3-3

2024/5/24 22:50:14

Urms = 220.1 V P = 58.90 W
Irms = 0.288 A pf = 0.929

Range: 10 A
V-nom: 220 V
TestTime: 10 min (100%)

Test completed, Result: PASSED

Urms = 220.1V Freq = 49.987 Range: 10 A
Irms = 0.288A Ipk = 0.498A cf = 1.729
P = 58.90W S = 63.41VA pf = 0.929

Test - Time : 1 x 10min = 10min (100 %)

LIN (Line Impedance Network) : L: 0.24ohm +j0.15ohm N: 0.16ohm +j0.10ohm

Limits : Plt : 0.65 Pst : 1.00
dmax : 4.00 % dc : 3.30 %
dtLim: 3.00 % dt>Lim: 500ms

Test completed, Result: PASSED

	Pst	P3s	Fli	dmax [%]
1	0.072	0.010	0.000	0.000

4. EMC IMMUNITY TEST

4.1 STANDARD COMPLIANCE/SEVERITY LEVEL/CRITERIA

Tests Standard No.	Test Specification Level / Test Mode	Test Ports	Criteria
Electrostatic discharge IEC 61000-4-2 (ESD)	±8kV air discharge ±4kV contact discharge (Direct Mode)	Enclosure	B
	±4kV HCP discharge ±4kV VCP discharge (Indirect Mode)	Enclosure	B
Continuous RF electromagnetic field disturbances,swept test IEC 61000-4-3 (RS)	80 MHz to 1000 MHz 3V/m(unmodulated, r.m.s), 1 kHz, 80%, AM modulated	Enclosure	A
Continuous RF electromagnetic field disturbances,spot test IEC 61000-4-3 (RS)	1800 MHz, 2600MHz, 3500 MHz, 5000MHz(±1 %) 3V/m(unmodulated, r.m.s), 1 kHz, 80%, AM modulated	Enclosure	A
Electrical fast transient/burst immunity IEC 61000-4-4 (EFT)	±0.5kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency (100kHz Repetition Frequency for xDSL port)	Analogue/digital data ports (NOTE 2)	B
	±0.5kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency	DC network power ports (NOTE 2)	B
	±1 kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency	AC mains power ports	B

Surge immunity IEC 61000-4-5 (Surge)	Port Type: unshielded symmetrical		
	Apply: lines to ground		
	Primary protection is Intended ±1 kV and ±4 kV 10/700(5/320)Tr/Th μs	Analogue/digital data ports (NOTE 1) & (NOTE 2)	C
	Primary protection is not Intended ±1 kV 10/700(5/320) Tr/Th μs		C
	Port type: coaxial or shielded		
	Apply: shield to ground		
±0.5 kV 1.2/50(8/20) Tr/Th μs	Analogue/digital data ports (NOTE 1) & (NOTE 2)	B	
line to reference ground for each individual line: ±0.5 kV(peak) 1.2/50(8/20) Tr/Th μs	DC network power ports (NOTE 2)	B	
±1 kV(peak) 1.2/50(8/20) Tr/Th μs (line to line) ±2 kV(peak) 1.2/50(8/20) Tr/Th μs (line to earth or ground)	AC mains power ports	B	
Continuous induced RF disturbances IEC 61000-4-6 (CS)	0.15 MHz to 10 MHz 3V(unmodulated, r.m.s), 10 MHz to 30 MHz 3V to 1V(unmodulated, r.m.s), 30 MHz to 80 MHz 1V(unmodulated, r.m.s), 1kHz 80%, AM 150Ω source impedance	Analogue/digital data ports (NOTE 2)	A
	0.15 MHz to 10 MHz 3V(unmodulated, r.m.s), 10 MHz to 30 MHz 3V to 1V(unmodulated, r.m.s), 30 MHz to 80 MHz 1V(unmodulated, r.m.s), 1kHz 80%, AM 150Ω source impedance	DC network power ports (NOTE 2)	A
	0.15 MHz to 10 MHz 3V(unmodulated, r.m.s), 10 MHz to 30 MHz 3V to 1V(unmodulated, r.m.s), 30 MHz to 80 MHz 1V(unmodulated, r.m.s), 1kHz 80%, AM 150Ω source impedance	AC mains power ports	A

Power frequency magnetic field immunity IEC 61000-4-8 (PFMF)	50 Hz or 60Hz, 1A/m(r.m.s)	Enclosure	A
Voltage dips, short interruptions and voltage variations immunity IEC 61000-4-11 (Dips)	Voltage dips: Residual voltage<5% 0.5 cycle Residual voltage<70% 25 cycle(50Hz), 30 cycle (60Hz) Voltage interruptions: Residual voltage<5% 250 cycle (50Hz), 300 cycle (60Hz)	AC Power Ports	B C C
Broadband impulse noise disturbances,repitive (BIN-R)	0.15 MHz to 0.5 MHz 107 dBuV 0.5 MHz to 10 MHz 107 dBuV to 36 dBuV 10 MHz to 30 MHz 36 dBuV to 30 dBuV	Analogue/digital data ports (Applicable only to CPE xDSL ports)	A
	0.70 ms 8.3 ms(for 60Hz) 10 ms(for 50Hz)	Analogue/digital data ports (Apply period based on the AC mains frequency)	A
Broadband impulse noise disturbances,isolated (BIN-I)	0.15 MHz to 30 MHz 110 dBuV	Analogue/digital data ports (Applicable only to CPE xDSL ports)	B
	0.24 ms 10 ms 300 ms	Analogue/digital data ports (Apply all burst durations)	B

Note.

- 1) Applicable only to ports which, according to the manufacturer's specification, may connect directly to outdoor cables.
- 2) Applicable only to ports which, according to the manufacturer's specification, support cable lengths greater than 3 m.

4.2 GENERAL PERFORMANCE CRITERIA

According to **EN 55035** standards, the general performance criteria as following:

Criterion A	The equipment shall continue to operate as intended without operator intervention. No degradation of performance, loss of function or change of operating state is allowed below a performance level specified by the manufacturer when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criterion B	During the application of the disturbance, degradation of performance is allowed. However, no unintended change of actual operating state or stored data is allowed to persist after the test. After the test, the equipment shall continue to operate as intended without operator intervention; no degradation of performance or loss of function is allowed, below a performance level specified by the manufacturer, when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level (or the permissible performance loss), or recovery time, is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criterion C	Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions. A reboot or re-start operation is allowed. Information stored in non-volatile memory, or protected by a battery backup, shall not be lost.

4.3 ANNEX G (NORMATIVE) - AUDIO OUTPUT FUNCTION

4.3.1 PERFORMANCE CRITERIA

Performance criterion A:

For devices that support telephony functions the limits of Table G.3 shall apply.

With respect to Table G.3:

- the interference ratio (electrical or acoustic) shall meet the limits in column 3; or,
- the acoustic level of the demodulated audio shall be less than the limits in column 4; or,
- the digitally coded level of demodulated audio shall be less than limits in column 5; or,
- the analogue level of the demodulated audio shall be less than the limits in column 6.

Table G.3 – Performance criterion A – Limits for devices supporting telephony

Type of immunity test	Frequency range MHz	Acoustic or electrical interference ratio	Equivalent direct measurement		
			dB (SPL)	Digital dBm0	Analogue dBm
Conducted	0,15 to 30	-20 dB	55	-50	-50
	30 to 80	-10 dB	65	-40	-40
Radiated	80 to 1000	0 dB	75	-30	-30

For terminals connected to digital wired network ports (such as Ethernet, ISDN), measurements of the demodulated 1 kHz may be performed on a remote AE, ideally of the same design.

For all other devices:

The measured acoustic interference ratio and/or the measured electrical interference ratio during the test shall be –20 dB or better.

Performance criterion B:

Use the general performance criterion B. See GENERAL PERFORMANCE CRITERIA.

Performance criterion C:

Use the general performance criterion C. See GENERAL PERFORMANCE CRITERIA.

4.4 ELECTROSTATIC DISCHARGE IMMUNITY TEST (ESD)

4.4.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-2
Discharge Impedance	330 ohm / 150 pF
Required Performance	B
Discharge Voltage	Air Discharge: $\pm 2\text{kV}$, $\pm 4\text{kV}$, $\pm 8\text{kV}$ Contact Discharge: $\pm 4\text{kV}$
Polarity	Positive & Negative
Number of Discharge	20 times at each test point
Discharge Mode	Single Discharge
Discharge Period	1 second

4.4.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	ESD Generator	TESEQ	NSG 437	1726	Sep. 25, 2024

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.4.3 TEST PROCEDURE

The test generator necessary to perform direct and indirect application of discharges to the EUT in the following manner:

- a. The test shall be performed with single discharges. On each pre-selected point at least 10 single discharges (in the most sensitive polarity) shall be applied.

NOTE 1 The minimum number of discharges applied is depending on the EUT; for products with synchronized circuits the number of discharges should be larger.

For the time interval between successive single discharges an initial value of 1 s is recommended. Longer intervals may be necessary to determine whether a system failure has occurred.

NOTE 2 The points to which the discharges should be applied may be selected by means of an exploration carried out at a repetition rate of 20 discharges per second, or more.

Vertical Coupling Plane (VCP):

The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to, and positioned at a distance 0.1m from, the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.

Horizontal Coupling Plane (HCP):

The coupling plane is placed under to the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.


- b. For TABLE-TOP equipment:

The configuration consisted of a wooden table 0.8 meters high standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system. A Horizontal Coupling Plane (1.6m x 0.8m) was placed on the table and attached to the GRP by means of a cable with 940k total impedance. The equipment under test was installed in a representative system as described in IEC 61000-4-2, and its cables were placed on the HCP and isolated by an insulating support of 0.5mm thickness. A distance of 1-meter minimum was provided between the EUT and the walls of the laboratory and any other metallic structure.

4.4.4 DEVIATION FROM TEST STANDARD

No deviation

4.4.5 TEST SETUP



4.4.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-3


Mode	Air Discharge								Contact Discharge					
	2kV		4kV		8kV		- kV		4kV		- kV		- kV	
Location	P	N	P	N	P	N	P	N	P	N	P	N	P	N
1	A	A	A	A	A	A	-	-	A	A	-	-	-	-
2	A	A	A	A	A	A	-	-	A	A	-	-	-	-
3	A	A	A	A	A	A	-	-	-	-	-	-	-	-
4	A	A	A	A	A	A	-	-	-	-	-	-	-	-
5	A	A	A	A	A	A	-	-	-	-	-	-	-	-
6	A	A	A	A	A	A	-	-	-	-	-	-	-	-
Criteria	B								B					
Result	A								A					

Mode	HCP Contact Discharge						VCP Contact Discharge					
	4kV		- kV		- kV		4kV		- kV		- kV	
Location	P	N	P	N	P	N	P	N	P	N	P	N
Left side	A	A	-	-	-	-	A	A	-	-	-	-
Right side	A	A	-	-	-	-	A	A	-	-	-	-
Front side	A	A	-	-	-	-	A	A	-	-	-	-
Rear side	A	A	-	-	-	-	A	A	-	-	-	-
Criteria	B						B					
Result	A						A					

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) N/A - denotes test is not applicable in this test report

PHOTO(S) SHOWN THE LOCATION(S) OF ESD EVALUATED







4.5 RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD IMMUNITY TEST (RS)

4.5.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-3
Required Performance	A
Frequency Range	80 MHz - 1000 MHz, 1800 MHz, 2600 MHz, 3500 MHz, 5000MHz ($\pm 1\%$)
Field Strength	3 V/m(unmodulated, r.m.s)
Modulation	1 kHz Sine Wave, 80%, AM Modulation
Frequency Step	1% of the preceding frequency.
Polarity of Antenna	Horizontal and Vertical
Test Distance	3 m
Antenna Height	1.55 m
Dwell Time	3 seconds

4.5.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Stacked Double Log.-Per.Antenna	Schwarzbeck	STLP 9129	00210	N/A
2	Power amplifier	RFLIGHT	NTWPA-0081030 0	21113246	Jan. 19, 2025
3	Power amplifier	RFLIGHT	NTWPA-1060100 P	21123268	Jan. 19, 2025
4	MXG Vector Signal Generator	Keysight	N5181A	MY50144565	Jul. 07, 2024
5	Measurement Software	Tonscend	TS+	N/A	N/A
6	UPV Audio Analyzer	R&S	UPV	101941	Jul. 07, 2024
7	Free-field 1/2"Microphone	B&K	4190-L-001	3230388	Oct. 22, 2024
8	Conditioning Amplifier	B&K	-2690--0F2-	3313664	Oct. 24, 2024

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.5.3 TEST PROCEDURE

The EUT and support equipment are in a fully-anechoic chamber.

The testing distance from antenna to the EUT was 3 meters.

For TABLE-TOP equipment:

The EUT installed in a representative system as described in IEC 61000-4-3 was placed on a non-conductive table 0.8 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

- The field strength level was 3 V/m(unmodulated, r.m.s).
- The frequency range is swept from 80 MHz to 1000 MHz, with the signal 80%amplitude modulated with a 1 kHz sine wave. Where the frequency range is swept incrementally, the step size was 1% of the preceding frequency.
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.
- The test was performed with the EUT exposed to both vertically and horizontally polarized fields on each of the four sides.

For Acoustic measurements:


- Apply an appropriate input signal to the EUT so that a sine wave (tone) at the frequency that will be used to modulate the applied disturbance (typically 1 kHz) is generated from the port under test at a level equal to the acoustic reference level.
- Record the resulting dB (SPL) level (or other appropriate dB unit) as the value of L_0 .
(BTL lab uses the software to take L_0 as the reference value and make it return to zero.)
- Change the input to the EUT so that the port under test is silent, or represents silence. This change shall not alter the terminating impedance at the EUT's input.
- Apply the RF disturbance to the applicable port of the EUT and record the resulting demodulated audio level in dB (SPL) (or other dB unit used in step d)) as the value of L_1 .
- Ensure that non-linear processing does not impact the measurements.
- Calculate the acoustic interference ratio using the following formula:
Acoustic interference ratio = $L_1 - L_0$.
(For step e-f, BTL lab proceeds the test with software and calculate Acoustic interference ratio = $L_1 - L_0$).

4.5.4 DEVIATION FROM TEST STANDARD

No deviation


4.5.5 TEST SETUP

- For Continuous induced RF disturbances




For Audio output function

(1) Audio output port




The filter is the audio filter specified in G.6.1 and is typically incorporated into the audio meter. Additional filtering might be necessary to ensure that the RF disturbance signal does not interfere with the measurement.

(2) Loudspeaker



The filter is the audio filter specified in G.6.1 and is typically incorporated into the audio meter. Additional filtering might be necessary to ensure that the RF disturbance signal does not interfere with the measurement.



The microphone is connected via the cable to a suitable amplifier. Ensure that there is minimal acoustic loss between EUT and microphone.

4.5.6 TEST RESULTS


Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-3

Frequency Range (MHz)	RF Field Position	R.F. Field Strength	Modulation	Azimuth	Criterion	Result
80 - 1000	H / V	3V/m	AM Modulated 1000Hz, 80%	0	A	
				90		
				180		
				270		
1800, 2600, 3500, 5000 (±1%)	H / V	3V/m	AM Modulated 1000Hz, 80%	0	A	
				90		
				180		
				270		


For Audio output function

(1) Audio output port:

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_ Vertical_Left




Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_ Horizontal_Left




(2) Loudspeaker:

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_ Vertical_Left



Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_ Horizontal_Left



4.6 ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST (EFT)

4.6.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-4
Required Performance	B
Test Voltage	AC mains power ports: ± 1 kV
Polarity	Positive & Negative
Impulse Frequency	5 kHz
Impulse Wave shape	5/50 ns
Burst Duration	15 ms
Burst Period	300 ms
Test Duration	1 min.

4.6.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Fast Transient Burst Simulator	Prima	EFT61004T A	PR201843360	Jul. 07, 2024

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.6.3 TEST PROCEDURE

For TABLE-TOP equipment:


The configuration consisted of a wooden table (0.8m high) standing on the Ground Reference Plane and should be located 0.1 m $\pm$ 0.01m above the Ground Reference Plane. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system. A minimum distance of 0.5m was provided between the EUT and the walls of the laboratory or any other metallic structure.

- Both positive and negative polarity discharges were applied.
- The duration time of each test sequential was 1 minute.

4.6.4 DEVIATION FROM TEST STANDARD

No deviation

4.6.5 TEST SETUP



4.6.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-3

EUT Ports Tested		Polarity	Repetition Frequency	Test Level 1kV	Criterion	Result
AC Power Port	Line (L)	+	5 kHz	A	B	A
		-	5 kHz	A		
	Neutral (N)	+	5 kHz	A	B	A
		-	5 kHz	A		
	Ground (PE)	+	5 kHz	A	B	A
		-	5 kHz	A		
	L+N	+	5 kHz	A	B	A
		-	5 kHz	A		
	L+PE	+	5 kHz	A	B	A
		-	5 kHz	A		
	N+PE	+	5 kHz	A	B	A
		-	5 kHz	A		
	L+N+PE	+	5 kHz	A	B	A
		-	5 kHz	A		

4.7 SURGE IMMUNITY TEST (SURGE)

4.7.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-5
Required Performance	B(AC mains power ports)
Wave-Shape	1.2/50(8/20) Tr/Th μ s combination wave
Test Voltage	AC mains power ports: ± 0.5 kV, ± 1 kV, ± 2 kV
Generator Source Impedance	2 Ω of the low-voltage power supply network. 12 Ω (10 Ω +2 Ω) of the low-voltage power supply network and ground.
Phase Angle, Polarity and Number of Tests	Five positive pulses line-to-neutral at 90°phase Five negative pulses line-to-neutral at 270°phase Five positive pulses line-to-earth at 90°phase Five negative pulses line-to-earth at 270°phase Five negative pulses neutral-to-earth at 90°phase Five positive pulses neutral-to-earth at 270°phase
Pulse Repetition Rate	1 time / min

4.7.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Lightning Surge Generator	Prima	SUG61005TB	PR210655102	Jul. 07, 2024
2	Measurement Software	Prima	SUG_Series	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.7.3 TEST PROCEDURE

a. For EUT power supply:

The surge is to be applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks are required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines, and to provide sufficient decoupling impedance to the surge wave. The power cord between the EUT and the coupling/decoupling networks shall be 2meters in length (or shorter).

b. For test applied to unshielded unsymmetrically operated interconnection lines of EUT :

The surge is applied to the lines via the capacitive coupling. The coupling /decoupling networks shall not influence the specified functional conditions of the EUT. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).


c. For test applied to unshielded symmetrically operated interconnection /telecommunication lines of EUT :

The surge is applied to the lines via gas arrestors coupling. Test levels below the ignition point of the coupling arrestor cannot be specified. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

4.7.4 DEVIATION FROM TEST STANDARD

No deviation

4.7.5 TEST SETUP



4.7.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-3

Wave Form EUT Ports Tested		1.2/50(8/20)Tr/Thµs						Criterion	Result
		Polarity	Phase	Voltage					
				0.5kV	1kV	-- kV	-- kV		
AC	L – N	+	90°	A	A	-	-	B	A
		-	270°	A	A	-	-		

Wave Form EUT Ports Tested		1.2/50(8/20)Tr/Thµs						Criterion	Result
		Polarity	Phase	Voltage					
				0.5kV	1kV	2kV	-- kV		
AC	L – PE	+	90°	A	A	A	-	B	A
		-	270°	A	A	A	-		
	N – PE	-	90°	A	A	A	-	B	A
		+	270°	A	A	A	-		

4.8 IMMUNITY TO CONDUCTED DISTURBANCES, INDUCED BY RADIO-FREQUENCY FIELDS TEST (CS)

4.8.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-6
Required Performance	A
Frequency Range&Field Strength	0.15 MHz - 10 MHz: 3V (unmodulated, r.m.s.) 10 MHz - 30 MHz: 3V to 1V (unmodulated, r.m.s.) 30 MHz - 80 MHz: 1V (unmodulated, r.m.s.)
Modulation	1 kHz Sine Wave, 80%, AM Modulation
Frequency Step	1 % of the preceding frequency value
Dwell Time	3 seconds

4.8.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Test system for conducted immunity	TESEQ	NSG4070	61322	Jul. 07, 2024
2	Measurement Software	Farad	EZ-CS (Ver:B-3.1)	N/A	N/A
3	Coupling Decoupling Network	TESEQ	CDN M016	61183	Jul. 07, 2024
4	UPV Audio Analyzer	R&S	UPV	101941	Jul. 07, 2024
5	Free-field 1/2"Microphone	B&K	4190-L-001	3230388	Oct. 22, 2024
6	Conditioning Amplifier	B&K	-2690--0F2-	3313664	Oct. 24, 2024

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.8.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.

The other condition as following manner:

- The field strength level was 3 V (unmodulated, r.m.s.)
- The frequency range is swept from 150 kHz to 80 MHz, with the signal 80%amplitude modulated with a 1 kHz sinewave. Where the frequency range is swept incrementally, the step size shall not exceed 1 % of the preceding frequency value.
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.


For Acoustic measurements:

- Apply an appropriate input signal to the EUT so that a sine wave (tone) at the frequency that will be used to modulate the applied disturbance (typically 1 kHz) is generated from the port under test at a level equal to the acoustic reference level.
- Record the resulting dB (SPL) level (or other appropriate dB unit) as the value of L_0 . (BTL lab uses the software to take L_0 as the referecne value and make it return to zero.)
- Change the input to the EUT so that the port under test is silent, or represents silence.This change shall not alter the terminating impedance at the EUT's input.
- Apply the RF disturbance to the applicable port of the EUT and record the resulting demodulated audio level in dB (SPL) (or other dB unit used in step d)) as the value of L_1 .
- Ensure that non-linear processing does not impact the measurements.
- Calculate the acoustic interference ratio using the following formula:
Acoustic interference ratio = $L_1 - L_0$.
(For step e-f, BTL lab proceeds the test with software and calculate Acoustic interference ratio = $L_1 - L_0$).

4.8.4 DEVIATION FROM TEST STANDARD


No deviation

4.8.5 TEST SETUP




For Audio output function

(1) Audio output port




The filter is the audio filter specified in G.6.1 and is typically incorporated into the audio meter. Additional filtering might be necessary to ensure that the RF disturbance signal does not interfere with the measurement.

(2) Loudspeaker



The filter is the audio filter specified in G.6.1 and is typically incorporated into the audio meter. Additional filtering might be necessary to ensure that the RF disturbance signal does not interfere with the measurement.



The microphone is connected via the cable to a suitable amplifier. Ensure that there is minimal acoustic loss between EUT and microphone.

4.8.6 TEST RESULTS


Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-3

Test Ports (Mode)	Freq.Range (MHz)	Field Strength	Modulation	Criteria	Results
AC mains power ports	0.15 - 10	3V	AM Modulated 1000Hz, 80%	A	
	10 - 30	3V to 1V			
	30 - 80	1V			

For Audio output function


(1) Audio output port:

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_CDN_M3



(2) Loudspeaker:

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_CDN_M3



4.9 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST (PFMF)

4.9.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-8
Required Performance	A
Frequency Range	50/60Hz
Field Strength	1 A/m
Observation Time	1 minute
Inductance Coil	Rectangular type, 1mx1m

4.9.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Power frequency magnetic field interferes with main engine	3ctest	MFS 400	ES045000821015	Aug. 14, 2024
2	Magnetic field generator module	3ctest	MFT400	ES046000121015	Aug. 14, 2024
3	magnetic field coil	3ctest	TCXS111	TCXS21070924	Aug. 14, 2024

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.9.3 TEST PROCEDURE

For TABLE-TOP equipment:

The equipment shall be subjected to the test magnetic field by using the induction coil of standard dimension (1 m x 1 m). The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.


The other condition as following manner:

- The equipment cabinets shall be connected to the safety earth directly on the GRP via the earth terminal of the EUT.
- The cables supplied or recommended by the equipment manufacturer shall be used. 1 meter of all cables used shall be exposed to the magnetic field.

4.9.4 DEVIATION FROM TEST STANDARD

No deviation

4.9.5 TEST SETUP



4.9.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-3

50Hz

Test Mode	Test Level	Antenna aspect	Duration	Criteria	Results
Enclosure	1 A/m	X	60s	A	A
Enclosure	1 A/m	Y	60s	A	A
Enclosure	1 A/m	Z	60s	A	A

60Hz

Test Mode	Test Level	Antenna aspect	Duration	Criteria	Results
Enclosure	1 A/m	X	60s	A	A
Enclosure	1 A/m	Y	60s	A	A
Enclosure	1 A/m	Z	60s	A	A

4.10 VOLTAGE DIPS, SHORT INTERRUPTIONS AND VOLTAGE VARIATIONS IMMUNITY TEST (DIPS)

4.10.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-11
Required Performance	Voltage dips: B (For <5% residual voltage, dips) C (For 70% residual voltage, dips) C (For <5% residual voltage, Interruptions)
Interval between Event	Ten seconds
Phase Angle	0°/180°
Test Cycle	3 times

4.10.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Cycle Sag Simulator	Prima	DRP61011TA	PR21076614	Jul. 07, 2024

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


4.10.3 TEST PROCEDURE

The EUT shall be tested for each selected combination of test levels and duration with a sequence of three dips/interruptions with intervals of 10 s minimum (between each test event). Each representative mode of operation shall be tested. Abrupt changes in supply voltage shall occur at zero crossings of the voltage waveform.

4.10.4 DEVIATION FROM TEST STANDARD

No deviation

4.10.5 TEST SETUP



4.10.6 TEST RESULTS

Test Voltage	AC 100V/50Hz, AC 230V/50Hz, AC 240V/50Hz
Test Mode	Mode 1-3



AC 100V/50Hz				
Item	Residual Voltage	Cycle	Criteria	Results
Voltage dips	<5%	0.5	B	A
Voltage dips	70%	25	C	C
Voltage Interruption	<5%	250	C	C

AC 230V/50Hz				
Item	Residual Voltage	Cycle	Criteria	Results
Voltage dips	<5%	0.5	B	A
Voltage dips	70%	25	C	A
Voltage Interruption	<5%	250	C	C



AC 240V/50Hz				
Item	Residual Voltage	Cycle	Criteria	Results
Voltage dips	<5%	0.5	B	A
Voltage dips	70%	25	C	A
Voltage Interruption	<5%	250	C	C

5. EUT TEST PHOTO



Radiated emissions up to 1 GHz




Radiated emissions above 1 GHz




Conducted emissions AC mains power port



Harmonic current




Voltage fluctuations (Flicker)




Electrostatic discharge immunity



Radiated, radio-frequency, electromagnetic field immunity – Up to 1GHz




Radiated, radio-frequency, electromagnetic field immunity – Above 1GHz




Electrical fast transient/burst immunity - AC




Surge immunity - AC




Immunity to conducted disturbances, induced by radio-frequency fields - AC



Power frequency magnetic field immunity



Voltage dips, short interruptions and voltage variations immunity



End of Test Report